

NE Griffin Oaks Street Pavement Replacement

Location: NE Griffin Oaks Street from NE 15th to NE 25th Avenue

About

The pavement on NE Griffin Oaks had exceeded its lifespan and was failing.

Improvements

This project replaced the old pavement and is designed with a 40-year lifespan. Drainage improvements were also completed to avoid future excavation in the newly replaced concrete street. The project included the replacement or installation of 10 catch basins, 1,700 feet of storm pipe, and eight manholes.

Project Funding Sources

The project was funded by the Transportation Utility Fee (TUF) and Surface Water Management Local Service Fee (LSF).

Project Timeline

Summer 2017 – spring 2018

Project Cost

Total Project Cost: \$2,154,070.32

Funded by LSF: \$361,147.54



Before



After